

## Article

# BIM-Integrated Construction Operation Simulation for Just-In-Time Production Management

WoonSeong Jeong <sup>1</sup>, Soowon Chang <sup>2</sup>, JeongWook Son <sup>1,\*</sup> and June-Seong Yi <sup>1</sup>

<sup>1</sup> Department of Architectural Engineering, Ewha Womans University, 52, Ewhayeodae-Gil, Seodaemun-Gu, Seoul 03760, Korea; ph.d.wsj@gmail.com (W.J.); jsyi@ewha.ac.kr (J.-S.Y.)

<sup>2</sup> School of Building Construction, Georgia Institute of Technology North Avenue, Atlanta, GA 30332, USA; soowonch@gatech.edu

\* Correspondence: jwson@ewha.ac.kr; Tel.: +82-2-3277-3577

Academic Editors: Vivian W. Y. Tam and Marc A. Rosen

Received: 11 October 2016; Accepted: 27 October 2016; Published: 29 October 2016

**Abstract:** Traditional construction planning, which depends on historical data and heuristic modification, prevents the integration of managerial details such as productivity dynamics. Specifically, the distance between planning and execution brings cost overruns and duration extensions. To minimize variations, this research presents a Building Information Modeling (BIM)-integrated simulation framework for predicting productivity dynamics at the construction planning phase. To develop this framework, we examined critical factors affecting productivity at the operational level, and then forecast the productivity dynamics. The resulting plan includes specific commands for retrieving the required information from BIM and executing operation simulations. It consists of the following steps: (1) preparing a BIM model to produce input data; (2) composing a construction simulation at the operational level; and (3) obtaining productivity dynamics from the BIM-integrated simulation. To validate our framework, we applied it to a structural steel model; this was due to the significance of steel erections. By integrating BIM with construction operation simulations, we were able to create reliable construction plans that adapted to project changes. Our results show that the developed framework facilitates the reliable prediction of productivity dynamics, and can contribute to improved schedule reliability, optimized resource allocation, cost savings associated with buffers, and reduced material waste.

**Keywords:** productivity dynamics; building information modeling; computer simulation; Just-In-Time; lean construction; data reuse

## 1. Introduction

Due to the increasing size and complexity of construction projects, traditional construction planning is no longer sufficient for producing workable plans that incorporate all necessary project details, such as design complexities, learning curves, and the coordination process. Such traditional construction methods require construction managers to utilize data from previous projects and make heuristic adjustments to establish on-site construction plans. However, with the radical shifts now being seen, construction planning that refers to previous projects' data cannot ensure the predicted level of productivity. Since construction projects have become more complex [1], managers' heuristics cannot encompass all of the necessary managerial and operational details. On-site work now suffers from constant modifications and changes to project conditions [2]. Such inadequate planning can result in delays [3] and cost overruns stemming from on-site operational problems.

This variability between planned and actual performance results in managerial inefficiency and, ultimately, lower-quality outcomes. Such differences lead to the supply of materials not coinciding with demand on the construction site; construction managers must then wrestle with an excess or lack

of materials. If the actual performance is greater than expected, materials become scarce and labor and equipment are wasted. On the other hand, if the actual performance is lower than expected, materials become excessive; construction costs then increase due to interest accrual and inventory management. Thus, reliable planning is extremely important to managerial efficiency and waste reduction. However, since construction projects are inherently dynamic and complex, the work productivity on site can vary daily, according to the type and number of mitigating factors [4,5]. Productivity dynamics can proliferate such variations between planned and actual production, resulting in an exacerbation of on-site problems.

Since productivity on construction sites is dynamic, it is challenging to develop sufficiently reliable construction plans. Each construction project is unique and complex. First, projects include numerous risks and uncertainty [6]. For instance, developments differ in location, design, level of skilled labor required, and team composition. The newness of the construction environment also adds unknowns to the execution process, so that planning based on historical data cannot guarantee the expected performance. This persistent newness results in frequent modifications to the planned schedule. Also, a variety of operational and managerial factors influence productivity. Construction work involves multiple processes and the complex interactions of a wide variety of components that are connected by nonlinear relationships [5]. Moreover, since a construction project involves numerous stakeholders (including owners, designers, contractors, and the government), coordination of all of the relevant participants can be challenging [7]. Finally, construction projects operate under numerous constraints, in dynamic environments, and require the coordination of multiple tasks [8]. Such complexity adds unpredictability, and prudent planning is required.

Reliable predictions of productivity at the operational level minimize uncertainties, facilitate efficiency, and decrease waste in terms of time, cost, and materials. However, “construction companies still lack the ability to properly plan, estimate, and execute projects in a consistent, efficient, and reliable manner” [2]. Existing planning and control techniques are insufficient for predicting reliable and adequate on-site performance. However, computer simulations can be used to improve a plan’s reliability, by explicitly incorporating performance factors and mutual causal relationships. Such simulations can be utilized to quantify and validate the efficiency of the construction process [6]. In addition, simulation models represent the: (1) overall logic of the multitude of activities required to construct a building; (2) resources involved in performing the work (e.g., labor, equipment, management, etc.); and (3) environment in which the project is being built (e.g., site conditions, labor pool, market situation, etc.) [9]. Using computer simulation tools allows construction managers to build consistent plans that consider critical productivity factors.

Furthermore, computer simulations automate the planning process, allowing for the integration of Building Information Models (BIM) that contain all of the information necessary for development. BIM design applications are more than just design tools; most BIM design applications also interface with other applications, allowing for energy analyses, cost estimations, and so on [10]. With the increasing amount of information available and BIM’s improved process annotations, information visualization has become central to the overall construction process [10]. In this context, integrating construction operation simulations with BIM would facilitate time and cost efficiency, and generally streamline the process.

In this regard, our research developed a BIM-integrated simulation framework for predicting reliable productivity dynamics by considering the factors that affect productivity at the operational level. Our BIM-integrated planning framework alleviates the difficulties that currently plague reliable construction planning, and allows for managerial efficiency as well as technical advancement. Above all, since BIM is a digital representation of the functional and physical characteristics of a building [11], it allows for the early incorporation of the unique characteristics of a building into the planning process. Also, since simulation models represent the comprehensive production process, including the dynamic and complex interaction of sub-processes [12], our framework allows us to synthetically consider diverse factors and repeatedly run construction project in a virtual space,

without risk. In the BIM-integrated simulation framework suggested here, simulations were fed data on the building elements that had already been generated by the BIM tool. The complete simulation performed the construction operation in a virtual world, and generated accurate forecasts of productivity dynamics that were more reliable than those developed by traditional methods.

## 2. Literature Review

This chapter reviews current studies on the use of computer simulation in construction, lean construction practices, and BIM applications used in our BIM-integrated simulation framework for Just-In-Time production planning. First of all, whereas computer simulation techniques can now be combined with advanced tools to analyze construction projects, difficulties with modeling simulations and unreliable data usage continue to inhibit the application of simulations in the construction management field. Additionally, while the construction industry has improved in many ways ranging from management practices to technical developments, to apply lean principles, lean construction should be emphasized (including all parties along the supply chain). While BIM's benefits to the construction industry are clear, its utilization in the construction management domain remains narrow.

### 2.1. Computer Simulation in Construction

Increasingly, simulation models are being used as problem-solving and decision-making tools in many industries, especially manufacturing [13]. Simulation has also long been an established method for analyzing both production and logistics [14]. Particularly, the manufacturing industry has successfully implemented simulations to improve production processes [15]. The popularity of simulation stems from its ability to make models of complex systems [16]. Simulations offer realistic representations of the interactions among a variety of systems' diverse components [16]. Despite these advantages, in the construction industry, the use of simulation for planning purposes has been largely limited to academic research. This is because simulation modeling is a time-consuming and error-prone process [12,17,18].

Certain researchers have argued that 4D simulations should be considered appropriate for use in the construction industry. However, 4D simulations only allow for the visualization of construction schedules [19]. In this research, we used 4D models instead of 4D simulations; references to "simulations" should be understood as including discrete-event simulations, system dynamics, agent-based simulations, and multi-method simulations. Currently, schedules used to establish 4D models are created via traditional construction planning methods, using historical data and heuristic adjustments. Thus, 4D models cannot offer either optimal or reliable plans; they remain on the level of visualization, not planning. If schedules are not developed in a reliable manner, construction managers can only use 4D models as visual communication tools and not as facilitators of planning, analyzing, and decision-making. To address the current limitations in this area, we have employed computer simulations as a means of developing construction plans and providing reliable schedules to 4D models.

There has been a substantial body of research on applying computer simulation technology to the construction field. The first simulation approach developed in this area was called CYCLONE [20], which can be used to model simple cyclic networks. For example, micro-CYCLONE simulations were used to analyze concrete batch plant operations according to resource combinations and distances [21]. However, this system was too simple to accurately model recourses, and thus tended to manipulate them in the model [9]. Then, with the development of object-oriented process simulation, simulation tools were improved to create more practical models with better user interfaces and the flexibility to adjust the model's scope; as a result, reliability improved. AbouRizk and Hajjar [22] introduced Symphony as a simulation language. Exploiting the possibilities of this new simulation tool, researchers suggested a production-based framework using simulations to establish ideal project execution plans; they also discussed the requirements for extending the scope of such simulations [2]. Subsequently, researchers have attempted to integrate simulation technology with other tools [9]. One example

was the integration of 3D-CAD (Computer-Aided Design) with computer simulations to support decision making during construction [23]. Other researchers used discrete-event simulation for planning by designing construction operations and then visualizing the simulated operations in 3D [24]. With the advancements that have been made with modeling tools, the potential applications of computer simulation have increased [9]. For instance, simulation models can now simulate and analyze construction operations, and then support construction scheduling. Ultimately, they can predict the utilization of resources and identify logistics bottlenecks [25].

However, to utilize computer simulations in the construction industry, we first need to solve limitations such as difficulties with modeling from simulations and unreliable use of data. This research is an effort to minimize the effects of these limitations and convince practitioners of the merits of using simulations in the construction industry. If researchers built standard simulations of each construction operation's work, practitioners could use those simulations for planning by only modifying the parameters salient to the particular project. Additionally, by using BIM-provided information and integrating BIM with simulations, the reliability of the simulation's data usage would be greatly improved. Therefore, this research suggests a new methodology for establishing reliable construction plans via a convenient and practical BIM-integrated simulation framework.

## 2.2. Lean Construction

Lean production, which tries to eliminate any waste of materials, time, or effort from a production process, was developed by Toyota (a Japanese car manufacturing company) [26,27]. It stemmed from the need to create a system of production that responded to customers' orders (i.e., not mass production). This approach greatly increased Toyota's productivity. Consequently, many industries have attempted to adopt the concept. In the construction industry, lean production was introduced in the mid-1990s [27]. The major aims are the minimization of waste and maximization of value. Various tools, methods, and techniques are employed to accomplish these goals. Applying lean thinking to the construction field has led to the development of a variety of planning and control systems [28]. For example, Mao and Zhang [3] established a construction re-engineering process that combines lean principles and computer simulation techniques. Based on such principles, their research classified construction activities into conversion and flow activities instead of the value-added/non-value-added classification system that was standard; the resulting re-engineering process avoids confusion in classification [3]. In this context, the application of lean principles in the construction field can improve the efficiency of construction planning.

The most important lean principle is the minimization and eventual elimination of wasted time, money, equipment, etc. [29,30]. On construction sites, there are many kinds of waste, such as the time crews spend waiting to begin a project or reworking incorrectly completed tasks, and inefficient handling of materials, inventory and workspace [28]. According to queue game theory [31], these types of waste increase with variations in flow, which in construction affects the entire supply chain. Specifically, variations in the actual and expected outcomes result in the need for buffers to manage variability in orders. However, buffers mean wasted resources spent on management and control, even when the buffers are not absolutely necessary. These, the buffers increase the production cycle and extent of the project's duration and budget [31,32]. If managers fail to reliably predict production in the field, they cannot help but accept an excess or lack of stock. The alternative is to control their inventory by change-orders. As a means of preparing for this type of situation, suppliers employ some number of buffers to shield against change-orders. If this unreliable and unpredictable situation continues, participants along the supply chain cannot achieve suitable levels of cost- and time-efficiency; efficiency along the entire extent of the supply chain fails. Reliability in production allows all contractors to manage their work with a minimum of buffers, and implement Just-In-Time production. Reliable production achieves minimum waste by delivering the right quantity at the right time, maximizing the value for the client by minimizing cost overruns and duration extensions.



Reliable construction planning is essential to eliminating waste in construction projects. However, it is difficult to accurately predict the needs of a particular project, because of their inherent uniqueness and complexity. In addition, productivity cannot be predicted at a normal or static rate because it involves dynamic interactions and complicated variables that come together in a variety of complex systems [33]. Productivity dynamics generated from new labor, a unique learning curve, or changes in the site's conditions can all lead to waste. Therefore, construction managers should consider such variables when planning. To accomplish this goal, we developed a BIM-integrated simulation framework. This framework will assist in the prediction of productivity dynamics, contribute to minimizing inventory on site, and increase reliability with regards to orders. The result will be a decrease in buffers and a realization of the key principles of lean construction.

### *2.3. Application of BIM*

BIM is a remarkable technology regularly employed in the Architecture/Engineering/Construction (AEC) industry [34]. It was developed as a tool for engineers to use to generate and manage building information and facilitate three-dimensional design [35]. BIM applications are rapidly becoming more common in the construction industry because they are useful for reducing cost and time, and enhancing project quality [36]. The major merit of this technology is the visual enhancements it provides, which are useful means of facilitating communication among stakeholders. In addition to providing a means of visualizing 3D geometric expressions, BIM incorporates a variety of process data useful for analyzing constructability. Furthermore, in BIM, architectural design is integrated with energy simulations to efficiently and accurately apply simulation input [34]. Geometric information is also integrated into structural simulations to analyze structural safety; detailed models are produced that reflect the uniqueness and authenticity of a building without excessive geometric simplifications [37]. Likewise, BIM is utilized in many other aspects of construction, such as analyses of building energy, structure, and constructability.


Rapid improvements in BIM technology have made building performance evaluations easier and quicker to complete; for example, energy consumption [34,38] and structural design analyses [37], and structural evaluations during construction [39] use BIM data to obtain the details necessary for a thorough investigation of a building's performance. Construction management also uses BIM to assist in visual communication among all key parties, the integration necessary to obtain new managerial knowledge, and automation that improves managerial efficiency. Yet in spite of these important uses, in the construction management field BIM data continue to be utilized for only simple and partial purposes. For instance, according to a study on project scheduling via the integration of BIM with construction process simulations [1,19], researchers only used BIM data to obtain the quantities of materials needed. Although quantity takeoff data is necessary when determining the duration of the construction process [25], on its own it is not sufficient for reliable construction planning. Specifically, operational and managerial data are needed, such as workable hours, amount of skilled labor, level of difficulty, and so on.

## **3. Methodology**

### *3.1. Productivity Dynamics*

In the past, scheduling for the construction industry has been based on average historical data collected from similar projects and heuristic adjustments made by construction managers. Construction managers multiply the quantity of materials by unit of time, based on historical data, and then calculate the total duration of the work. Then, the quantity of materials is multiplied by duration; as a result, daily production and productivity is established. Afterwards, managers heuristically adjust their construction production plans in accordance with initial delays, learning effects, and the need for re-work. In actuality, though, such plans tend to be quite different from execution. Since construction work follows an outdoor, project-based production process, the environment cannot be controlled and

variability is prevalent [40]. This variability leads to cost overruns and on-site delays (see Figure 1). For instance, if production is greater than expected, resources are wasted; this waste leads to unexpected costs and work delays (see Figure 1). On the other hand, if production is lower than expected, established buffers are unnecessary; this extra inventory leads to unexpected managerial costs and non-value-adding activities that waste resources [40] (see Figure 1). The goals of lean construction can be achieved by reducing or reliably predicting output variability [40]. Thus, in order to minimize the cost overruns and delay extensions caused by differences in plan and execution, this research paper presents a BIM-integrated simulation framework for reliable production planning. This research will lead to all parties along the supply chain achieving the expected level of efficiency and reliable production plans for the construction site; as a result, the waste of time, money, equipment, and materials will be minimized.




**Figure 1.** A diagram of productivity dynamics.

### 3.2. BIM-Integrated Simulation Framework

Above, we explained why reliable production planning is important to achieving lean construction; it increases the efficiency of all parties involved in the construction project. Consequently, in this work we argue for the use of computer simulations as a production process assessment tool and BIM as a reliable data source. In the following section, we will present a BIM-integrated simulation framework for construction planning. Subsequently, we will demonstrate the methodology's usefulness in establishing accurate productivity dynamics.

#### 3.2.1. Design of BIM-Integrated Simulation


Construction managers usually develop their construction plans according to historical data and heuristic adjustments (see Figure 2).



**Figure 2.** Traditional construction planning process.

Since construction projects often differ in terms of design, site, and environment, historical data cannot guarantee the expected level of performance. Also, because a considerable number of factors influence construction productivity, managers' heuristics cannot incorporate all managerial and

operational details. Therefore, this traditional construction planning method cannot produce reliable plans that properly consider a project's uniqueness and complexity. To remedy this, we have designed a set of BIM-integrated simulation procedures that can be customized to produce accurate synthetic planning (see Figures 2 and 3).




**Figure 3.** Proposed construction planning process using the BIM-integrated simulation framework.

First, we prepared a BIM model that included building information such as materials, geometry, size, and so on. Then, we developed commands using BIM Application Programming Interface (API) (C#) to extract the BIM data and translate that information into resource data for the computer simulation. These data were then input into the construction operation simulation. Finally, we obtained productivity dynamics and used them in our production planning, scheduling, and resource allocation.

### 3.2.2. BIM-Integrated Simulation Framework

We developed a BIM-integrated simulation framework for predicting productivity dynamics and facilitating reliable production management. BIM offers reliable data for construction process simulations. By developing commands using the BIM API, we were able to extract BIM data and translate it into building data that could then be input into the simulation. Using BIM will allow construction managers to consider construction projects' unique characteristics such as materials, geometry, and quantity and quality of work needed. This will save construction managers both time and money.

The simulation consisted of the overall construction work process, critical factors affecting productivity, work resources, BIM data, and managerial setting information. By using Anylogic 7 (Anylogic Company: St. Petersburg, Russian, 2013), a remarkable simulation technology already in use in many industries, we were able to synthetically consider the complex conditions of a standard construction project and a substantial amount of data. By using this BIM-integrated simulation framework, construction managers will be able to develop reliable productivity dynamics from accurate data (see Figure 4); as a result, variations between planned and actual production will be minimized.



**Figure 4.** BIM-integrated simulation framework.

#### 4. Development of BIM-Integrated Simulation

In this section, we explain the specific procedures for applying a BIM-integrated simulation to a construction project.

##### 4.1. Preprocessing a BIM Model

BIM models contain construction information such as a building's geometry, size, type, and so on shown in Figure 5. To generate the BIM model for this research, we used Autodesk Revit 2015 (Autodesk: San Rafael, CA, USA, 2015). Autodesk Revit provides powerful .NET API, which we employed to extend the information embodied in the BIM model. We then retrieved the input data relating to the construction process simulation by programming the .NET framework in the C# programming language.





Figure 5. Autodesk Revit model combining the project's information.

##### 4.2. BIM2SIM Approach

We developed commands to extract and change BIM data in order to input the resource data needed for the construction process simulation. We used the .NET framework language C# to compose the BIM2SIM commands. These commands first accessed the BIM information and extracted the BIM data; then, they translated the BIM data into simulation input data. The BIM2SIM approach is depicted in Figure 6. The following procedures were required to extract the BIM data for our construction operation simulation.

- Produced a pre-built BIM model
- Developed code for extracting data from BIM
- Constructed a dataset sorted for the simulation
- Translated that dataset into simulation input data




**Figure 6.** Diagram of the BIM2SIM process.

#### 4.3. Construction Operation Simulation

After preparing a pre-built BIM model and composing commands using BIM's API, we developed a construction operational simulation shown in Figure 7. To build a reliable simulation, we first scrutinized various construction processes by conducting a thorough literature review, interviewing practitioners, and analyzing textbooks. Then, we identified the critical factors that influence operational work productivity. Using the information collected from our analysis, we built a conceptual simulation model as a scheme, listed the critical productivity factors, and developed an operational simulation using the Anylogic software. The resulting simulation tool is the first and only instrument to bring together discrete events, system dynamics, and agent-based simulations in one model development environment. Using the Anylogic simulation tool, we followed the steps listed below to develop and conduct the final construction operation simulation.

- Defined the work procedures for the construction operation
- Determined the critical factors affecting work productivity
- Developed the simulation
- Extracted the building data from BIM to conduct simulation
- Implemented the computer simulation



**Figure 7.** Diagram of the simulation development process.



## 5. Application for BIM-Integrated Simulation Method

In this section, we discuss the application of the BIM-integrated simulation method to a steel erection project, in order to examine the applicability of the method for actual construction projects. Steel erection is one of the most important processes on the construction site; it has critical effects on a project's duration and cost. Consequently, steel erection work is one of the most actively-managed areas; accuracy is essential to reliable production planning. Therefore, by applying this method to steel erection work, we were able to validate the applicability of the method and minimize any excess money and time that would need to be spent on this step of the construction.

### 5.1. Preprocessing BIM Data Used for Planning

We prepared a steel-structure BIM model for an actual construction project in Seoul. The building's area was approximately 390 m<sup>2</sup>, and the site area was approximately 650 m<sup>2</sup>. The building had a basement and four above-ground floors. The structure was steel-reinforced concrete. We only modeled the steel elements of the structure to test our method for steel erection work (see Figure 8). The BIM model offered all of the necessary information, such as the number of columns and beams, size, type of each material, geometric location, and so on. These data were then used for the construction simulation model.





Figure 8. BIM model used to test the structural steel model.

### 5.2. Implementing Commands Using BIM's API to Extract Building Information

After preparing the BIM model, we developed commands using BIM's API and the C# .NET framework languages; these commands were imported using the add-in tool from Autodesk Revit 2015. The commands allowed engineers to obtain the required information embodied in the BIM model. The commands translated the extracted building information into input resource data for use in the construction operation simulation. The procedures used to retrieve the building information can be found in Figure 9. This process saved time, money, and effort that would otherwise have been needed to reproduce the building data already in the BIM model.



**Figure 9.** Data retrieval process from the BIM model, and the input data preparation process.

### 5.3. Development of the Construction Operation Simulation

We composed a steel erection work simulation via a discrete-event simulation approach because steel erection work is generally performed as a sequence of events over time. However, we noticed that steel construction requires installed location factors such as height; thus, we interpreted steel to be a simple agent. We also conducted a literature review, expert interviews, and a textbook analysis to determine a reliable construction operation process and appropriately used the retrieved building data in the simulation environment. To properly express the steel erection work process, we first composed a simulation outline to serve as a blueprint. Then, we identified critical factors affecting work productivity by scrutinizing this type of work, interviewing experts, and reviewing the relevant literature. The Anylogic software was used to build the model. We arranged the simulation libraries and parameters into processes and resources, according to their properties. In the following section, we present our process for developing a steel erection work simulation on a construction site.

### 5.3.1. Composing the Simulation Outline

After a literature review, interviews with experts, and a textbook analysis, we built our scheme for steel erection work on a construction site (see Figure 10). The work was divided into four sectors and fifteen operational processes. The first sector involved transporting materials to the construction site. The second was the temporary erection of the columns. The third sector was the temporary erection of the beams. The final sector included installation of all erection materials. There were four processes included in the first phase: (1) transporting the steel to the site; (2) moving the steel to the stockyard; (3) unloading the steel; and (4) maintaining the steel in the stockyard. In the second phase, there were also four processes: (1) preparing the columns to be lifted; (2) the lifting columns; (3) arranging the columns to be correctly placed; and (4) temporarily erecting the columns. In the third phase, there were five processes: (1) installing the safety device; (2) preparing the beam materials to be lifted; (3) lifting the beams; (4) arranging the beams to be correctly placed; and (5) temporarily erecting the beams/girders. The final phase was divided into two processes: (1) gauging the verticality; and (2) erecting all materials.




Figure 10. Composing the simulation blueprint.

### 5.3.2. Finding the Factors Critical to the Construction Operation

We identified the critical factors that influence the productivity of steel erection work on construction sites. To verify the reliability of our conclusions, we analyzed textbooks, interviewed specialists, and reviewed the relevant literature on the topic. According to research in this field, the factors that impact steel work productivity are extremely complex and diverse, and include the constructability and completeness of the design, responsibility of the workers, surrounding conditions, construction period, site size, structure type, supply of the materials, height of the work, and so on.

Among these and other factors, we found six that were repeatedly stressed by the experts. (1) *The number of workable days*. Workable days are days in which it is possible to further the construction project; this exclude days with bad weather or during which unexpected accidents occur. This factor has a significant impact on productivity; it is directly connected to the time resource input value; (2) *Variety of erection materials used in the same area*. The more materials needed in a single area, the more time the project consumes; (3) *The capacity of the stockyard*. This factor influences the materials' supply cycle; (4) *The height of the project*. If the steel erection work is performed above the fifteenth floor, logistics of placement become so complex and the time spent lifting becomes so prolonged that productivity is always reduced; (5) *Access to a tower crane*. Steel erection work requires the use of a tower crane. Thus, easy access is a critical factor to productivity; (6) *Workers' level of skill*. Workers are diverse and unpredictable, and their efficiency and knowledge is critical to productivity.

### 5.3.3. Steel Erection Work Simulation

Using Anylogic, we created a simulation model based on a simulation outline and the above-discussed critical factors. The model was prepared as a discrete-event simulation (see Figure 11). Associations among the critical factors and simulation libraries were organized according to their relation. As mentioned above, we divided the steel erection work into four sectors and expressed each as a different line in the simulation model (see Figure 11). However, the specific simulation processes went far beyond the defined steps in the simulation outline, due to the dummy steps necessary to meaningfully control the flow of materials. The critical factors were defined as: 'schedule', 'numbersOfErect', 'capaOfStockYard', 'heightOfErect', 'availableTC', and 'workersSkill', which translated to workable days, number of erection materials, capacity of the stockyard, height of the project, access to a tower crane, and skill of the workers, respectively. The schedule and parameter simulation components in the Anylogic software were used to incorporate these factors into the simulation model.




Figure 11. Steel erection work simulation model in Anylogic.

Labor and equipment were defined as resources in Anylogic (see Figure 12). We initially divided labor into five categories: one foreman, two bolting workers, three welding workers, one worker to support the hooking materials, and one signal man to support the lifting. The initial number of workers was determined by analyzing the standard crew used in steel erection work. Additionally, we included one forklift, one tower crane, and small tools used for bolting. A forklift is used to move steel materials under 30 tons; however, it was not used in our simulation because the capacity of the forklift was not considered critical to productivity. A tower crane moves one steel beam at a time. Small tools are dummy resources and were included only to illustrate that tools were required for the bolt workers.




Figure 12. Types and number of resources needed for steel erection work.

#### 5.3.4. Simulation Libraries and Parameters

We determined that a number of components and parameters were necessary for steel erection work on a construction site. Both 'Source' and 'Sink' were essential to building the process model because 'Source' provided a starting point and 'Sink' an end point. Despite the volume of steel materials included in the process model, the 'carrying materials' sector was expressed as a single entity because it was all loaded onto a single truck. To bind the steel to a single entity, we used the 'Batch' component. 'MoveTo' was used to express a truck entering into a stockyard space. When the steel materials arrive at the stockyard, workers must spend time unloading them; we expressed this step as a 'Delay' component. To allocate a forklift before and after the unloading process, we added 'Seize' and 'Release' components. If materials needed to be detached from their delivery truck, we identified them individually via the 'Unbatch' component. We used the 'Queue' component to demonstrate when steel remained in the stockyard until it was required for erection.

In the second sector, the ‘temporary erecting column’ task, we selected the columns among the inventory in the stockyard via the ‘Pickup’ component. The columns could then be hooked to the lift, lifted, arranged in the correct spot, and temporarily erected. In the third sector, the ‘temporary erecting beam’ task, we followed a similar process. We first selected the beam materials via the ‘Pickup’ component, and then installed the safety equipment, hooked the beams to the lift, lifted the beams, arranged the beams on the correct spots, and then temporarily erected them.

Finally, the ‘erecting all materials’ sector followed a relatively simple set of two steps: checking the verticality of all of the materials, and firmly erecting all of the installed steel materials. In order to erect the beams after the columns were installed, we added a ‘Hold’ component between the first and second sectors. The blocking condition for ‘Hold’ was whether the number of columns in the batch was the same as the number of beams in the batch. From this component, we were able to prevent steel materials from jumping onto a ‘temporary erecting beam’ sector before the columns were erected. In Table 1, the specific simulation components and our process of naming are described.

**Table 1.** Simulation steps for steel erection work.

Simulation Components	Naming	Description
Source	source	Starting point of the process model
Batch	batch	Binding steels to one entity because requested steels are entered in one truck
MoveTo	truckEnter	Entering a truck
MoveTo	driveToUnload	Moving truck to a stockyard space
Seize	seizeSt	Allocating steels to forklift for unloading
Delay	unloading	Unloading step
Release	releaseSt	Releasing steels from forklift after unloading
Unbatch	unbatch	Detaching steels from a truck
Queue	managSt	A stockyard to load steals
Hold	hold	Holding steel entities to pass to erecting beams before erecting columns are completed
Pickup	pickupCol	Selecting the number of columns planned to be erected
Unbatch	unbatchCol	Selected one entity is divided to individual columns.
Service	hookCol	Hooking/Wiring column to tower crane
Service	liftColumn	Lifting columns one by one
Service	erectCol	Arranging columns on right point and erecting columns temporarily
Batch	batchCol	Binding erected columns as one entity to move onto next step when columns stretched to three stories are erected
Pickup	pickupBe	Selecting the number of beams planned to be erected
Unbatch	unbatchBe	Dividing selected one entity into individual beams.
Delay	equipSafety	Preparing safety materials
Service	hookBeam	Hooking/Wiring beam to tower crane
Service	liftBeam	Lifting beams one by one
Service	erectBeam	Arranging beams on right point and erecting beams temporarily
Batch	batchBe	Binding erected beams as one entity to move on next step when beams are erected
Delay	checkAll	Checking the vertical states of temporary erected materials
Service	erectAll	Installing all erected materials permanently
Sink	sink	Ending point of the process model

We presumed that 1 s in the simulation equated to 6 min in real time. We then defined the simulation input values and assumptions for each simulation step. Among these steps, we determined those directly related to productivity: ‘hookCol’, ‘liftColumn’, ‘erectCol’, ‘equipSafety’, ‘hookBeam’, ‘liftBeam’, ‘erectBeam’, ‘checkAll’, and ‘erectAll’. To determine the reliable productivity output provided by the simulation, we needed an accurate way of defining these nine steps. Through a literature review



and interviews with experts, we configured dependable values and an appropriate distribution for the steps presented in Table 2.

**Table 2.** Input values and assumptions.

Steps	Input Values	Description or Assumptions
source	1 entity every 5 s	Source depends on the schedule; this schedule will be defined after predicting reliable production plan
batch	numberOfCol + numberOfBeam (+dummySteel)	We assumed that columns and beams of each level are entered in one truck
truckEnter	None (Dummy step)	This step means that a truck enters a site. The speed can be limited during simulation
driveToUnload	None (Dummy step)	This step means that a truck moves in front of the stock yard for unloading. The speed can be limited during simulation
seizeSt	Resource sets: forklift	This step allocates steels to the resource (forklift).
unloading	* triangular(1, 5, 4)	This step is a dummy step because it is not directly related to measure productivity. Then, we assumed input values depending on various cases.
releaseSt	Release: all seized resources	This step releases steels from the resource (forklift)
unbatch	None	This step is the dummy step for recognizing steel entities individually by detaching them from one truck
managSt	Capacity = 'capaOfStockYard'	Its capacity is adjusted by the 'capaOfStockYard' parameter
hold	Blocking condition: hold.out.count() != batchBe.out.count();	This step holds steel materials for allocating to the proper sequence
pickupCol	Quantity: numberOfCol	This step picks up columns to perform 'temporary erecting columns work'
unbatchCol	None	This step is the dummy step for recognizing steel entities individually
hookCol	triangular(0.583, 1.167, 0.833)	We assume hooking column material one by one. Also, it requires the same amount of time with hookBeam
liftColumn	triangular(0.767, 1.067, 0.917)	This input distribution is acquired from analysis of previous literatures
erectCol	triangular(3.667, 6.167, 4.167)	This input distribution is acquired by cross-checking of previous literatures
batchCol	Size: numberOfCol	We bound columns on one floor plan into one batch
pickupBe	Quantity: numberOfBeam	This step picks up beams to perform 'temporary erecting beams work'
unbatchBe	None	This step is the dummy step for recognizing steel entities individually
equipSafety	1.667	expert interview
hookBeam	triangular(0.183, 0.44, 0.258)	We assume hooking a beam material one by one because of preventing torsion
liftBeam	triangular(0.769, 1.069, 0.919)	This input distribution is acquired from analysis of previous literatures
erectBeam	triangular(3.731, 4.000, 3.869)	This input distribution is acquired by cross-checking of previous literatures
batchBe	Size: numberOfBeam	We bound beams on one floor plan into one batch
checkAll	80	expert interview
erectAll	numberOfBeam * triangular(3.731, 4.000, 3.869)	The number of erecting materials installed is same as the number of temporary erecting beams
sink	None	Ending point

\* 1 s in simulation = 6 min in real time. \* triangular(min, max, mode).

Whereas the input distribution of the construction simulation fit the beta distribution [41], it was more difficult to obtain an amount of data sufficient to extract the beta distribution. Since triangular distribution is both simple and intuitive [42,43], we applied it as input data retrieved, based on data from previous literature (see Table 2). The triangular input data used for critical simulation steps were determined by cross-checking the previous literature on this topic. The values are presented in Table 3.


**Table 3.** Triangular input data for critical simulation steps.

Steps	Duration (Minutes in Real Time *)		
	Minimum	Most Likely (Mode)	Maximum
hookCol	3.500	5.000	7.000
liftColumn	4.600	5.500	6.400
erectCol	22.000	37.000	25.000
hookBeam	1.100	1.550	2.640
liftBeam	4.613	6.413	5.513
erectBeam	22.388	24.000	23.213
erectAll	22.388	24.000	23.213

\* 1 s in simulation = 6 min in real time.

### 5.3.5. Steel Agent Modeling

In the steel erection work model using discrete-event simulation (process-centric models), steel was used as an object in the process flow. We needed the amount of materials and the height of the erection, which were obtainable from the BIM model. After we obtained this information, we classified the steel materials according to their required order in the work process flow shown in Figure 13. First, we sorted the columns and beams. Then, the steel was divided according to separate floors because it needed to be installed according to the floor order. In the model presented in Figure 8, the columns were only installed on the basement level, so we created only one state for columns. Conversely, we prepared six states for the beams because they needed to be installed on all six floors. To classify these input values, we created two parameters, 'baselevel' and 'referenceLevel'. After developing the commands for extracting the BIM information, we stored the base level value of the columns in 'baselevel' and the reference level value of the beams in 'referenceLevel'. Since columns only had a base level and beams only had a reference level, these two parameters were all that were needed. Additionally, we reflected the height factor by dividing the state by floor.

**Figure 13.** Steel agent model composed using Anylogic.

#### 5.4. Running the BIM-Integrated Simulation

Within the Autodesk Revit 2015 environment, we opened the prepared BIM model and added in the commands described above. By executing the process, we obtained the simulation input data extracted from the BIM model and translated it into the simulation data format. Then, we opened the Anylogic simulation application and imported the simulation input data. We also imported the steel work process model. Next, the input data model was added to the steel work process simulation. In the Anylogic simulation environment, different files can be combined if they are written in an Anylogic simulation format such as alp. We then integrated the resource input data from BIM into the steel work process simulation, performed the steel erection work process simulation, and measured the column and beam erection productivities and the overall productivity of the erection. The entire process is presented in Figure 12. When we measured the productivity, we were able to obtain the optimal resource input combination by adjusting the input data. Consequently, the method enabled us to establish optimal resources and production plans that considered the construction project's uniqueness and complexity. Figure 14 shows the entire processes.




Figure 14. Processes running the BIM-integrated simulation method.

##### 5.4.1. Model Input and Assumptions

This section describes the model input data and assumptions that were made when we applied the BIM-integrated simulation to the actual steel installation work. Based on experts' opinions, we determined the simulation steps critical to the steel erection work simulation. These steps included hooking, lifting, erecting, installing safety equipment, and checking verticality. We analyzed the model's input values for these steps, found historical values in a previously-published case study,

cross-checked the data, then decided on minimum, maximum, and most likely values. This process was validated via the expert interviews.

We also assumed that there was one foreman who worked on the ground, one signalman for the signal, one worker who hooked the materials to the tower crane, two workers who erected the structure, and two workers who welded between the columns. We identified these values via a textbook analysis, expert interviews, and a review of the published literature on this topic. We presumed access to a forklift and tower crane, and analyzed the required use of this equipment by employing the basic analysis tools in the Anylogic simulation software. Also, the amount of materials the forklift and tower crane could move could be modified during the simulation because we considered them adjustable managerial values.

#### 5.4.2. Role of Critical Factors and Input Assumptions

As mentioned above, we identified six critical factors affecting productivity for steel erection work: the number of workable days, amount of materials, capacity of the stockyard, height of the erection, availability of a tower crane, and skill of the workers. These critical factors were divided into those that were and were not obtainable from BIM. Then, we determined how to consider unobtainable factors in the simulation model. The method we followed for reflecting all critical factors is presented in Table 4.

**Table 4.** Method for reflecting critical factors in the simulation model.

BIM Information	Critical Factors	Method to Reflect Critical Factors in the Simulation Model (Technical Method/Assumptions)
Obtainable	The number of erecting materials	The factor could be obtained from BIM model by executing commands
	The capacity of stockyard	The factor represented the number of capable stored steel materials in the stockyard, and it was considered as the managerial factor, so this value could be changed while running the simulation
	The workable day	The factor was unpredictable. Thus, if we predicted productivity, we could draw proper workable days
Unobtainable	The level of erecting height	We could obtain the height of erecting, but could not obtain the level of erecting height
	The availability of using the tower crane	We first supposed that there is one tower crane in a construction site. By calculating the utilization of tower crane resource, we could deduce proper utilization of the tower crane for steel erection work
	The skill of workers	The factor was also unpredictable. However, by supposing workers' skill, we could draw proper combination of workers' skill for steel erection work

We assumed that the height of the erection increased until Floor 3, then decreased to the roof; that is, the level of the columns in the basement was 1.2, while the levels of the erecting beams on the first, second, third, fourth, fifth, and sixth floors were 1.1, 1.0, 0.9, 1.2, 1.3, and 1.3, respectively. The production values were divided into these values to reflect the predicted steel work productivity. When we added the BIM information by using the above-mentioned commands, we classified the steel materials by their height; and then, each level of height was used to predict productivity. Additionally, since workers' levels of skill can be unpredictable, we extrapolated the optimal combination of skilled workers through an analysis of the various scenarios. Specifically, since the required number of workers will differ according to their skill, we applied a different number of workers to each process, compared their level of utilization, and extrapolated the optimal combination.

#### 5.4.3. Results from Running the BIM-Integrated Simulation Model


We executed the BIM-integrated simulation model and built graphs of the work productivity based on the model input values and critical factors determined from the above-mentioned assumptions. The amount of materials needed for each level was determined by using BIM's API commands.

We assumed that the capacity of the stockyard was more than the sum of the number of columns and beams in order to avoid restrictions from a limited stockyard. The difficulty of the work as the height increased was a productivity-impeding factor. The entire setup of all the critical factors is presented in Table 5.


**Table 5.** Simulation running conditions.

Setup Data	Base Case	Level 1	Level 2	Level 3	Level 4	Level 5	Level 6
The number of erecting materials	Column: 18	Beam: 32	Beam: 45	Beam: 45	Beam: 35	Beam: 25	Beam: 8
The capacity of stockyard	100						
The workable day	Extrapolation from the results of productivity on site						
The level of erecting height	1.2	1.1	1.0	0.9	1.2	1.3	1.3
The availability of using tower crane	Assumed one tower crane in the construction site. Extrapolated from the results of productivity on site						
The skill of workers	Maintain the initial number of workers						
	Foreman					1	
	Signal man					1	
	Workers for welding					2	
	Workers for bolting					2	
	Workers for hooking					1	

We performed our BIM-integrated simulation according to the simulation's running conditions shown in Figures 15–22. The installation sequence was according to height; that is, in the first set of erections, the beams on Levels 1, 2, and 3 were installed sequentially after installation of the first set of columns. Then, in the second set of erections, the beams on Levels 4, 5, and 6 were installed sequentially after installation of the second set of columns. The productivity of the beams varied according to the erection height. The difficulty of the work increased according to the following floor levels: 3, 2, 1, 4, 5, 6. Likewise, productivity increased according to the same sequence. While we supposed that the standard height was 1.0, we observed a difference if the difficulty level of work was varied more.




**Figure 15.** Productivity of the first column erection (89.187 s in simulation time).




**Figure 16.** Productivity of the second column erection (88.818 s in simulation time).







**Figure 17.** Productivity of beams in reference level 1 (131.244 s in simulation time).




**Figure 18.** Productivity of beams in reference level 2 (190.287 s in simulation time).




**Figure 19.** Productivity of beams in reference level 3 (190.000 s in simulation time).



**Figure 20.** Productivity of beams in reference level 4 (191.196 s in simulation time).



**Figure 21.** Productivity of beams in reference level 5 (22.400 s in simulation time).



**Figure 22.** Productivity of beams in reference level 6 (7.540 s in simulation time).

To allocate the production periods, we compared the times needed to complete each level of the erection work, as shown in Table 6. The values in Table 6 can also be seen in the graphs displayed in Figures 15–22. The total production time broadly depended upon the amount of erection materials. According to a comparison of the Levels 1 and 2 beam erection data, although Level 1 was more difficult, the total production time was shorter because the amount of necessary materials was less. In this regard, we found that the amount of materials has a greater influence on the production schedule than the height. Thus, we assumed the variation in difficulty to be 0.1, so if the variation increased, productivity would be controlled by height.

**Table 6.** Time to complete erection work.

Results	Base Case	Level 1	Level 2	Level 3	Level 4	Level 5	Level 6
The number of erecting materials	Column: 18	Beam: 32	Beam: 45	Beam: 45	Beam: 35	Beam: 25	Beam: 4
The level of erecting height	1.2	1.1	1.0	0.9	1.2	1.3	1.3
Time for completion (in Simulation)	Around 80 s	Around 130 s	Around 190 s	Around 190 s	Around 150 s	Around 98 s	Around 20 s
Time for completion (min)	480	780	1140	1140	900	588	120
Time for completion (h)	6.0	13.0	19.0	19.0	15.0	9.8	2.0

1 s in simulation = 6 min in real time.


## 6. Sensitivity Analysis

This section discusses the sensitivity analysis that tested the model's reaction to changes in the input parameters. We analyzed four critical factors: the amount of erection materials, stockyard capacity, height of the erection, and availability of a tower crane. Though there were a total of six factors found to be critical, workable days and workers' skill could not be defined or assumed before the simulation. These two factors can only be obtained by extrapolation from simulation results and/or analysis of previous research. Among the four impact factors, we analyzed the amount of erection materials and capacity of the stockyard because they could be modified by individuals involved in the construction project participants. For example, materials could be reduced by the strategic structural design of a structural designer, and the capacity of a stockyard could be adjusted by a strategic floor or path plan. Our sensitivity analysis considered these point of flexibility. The setup and results of this analysis are presented in Table 7 and visualized in Figure 23.

Traditionally, construction managers have accepted that productivity decreases when the amount of erection materials increases. However, according to our sensitivity analysis, productivity decreased but then recovered when the amount of erection materials regularly increased. On the other hand, when the amount was enough to disturb productivity, it decreased along with the extension of the capacity of the stockyard. With regards to construction planning, this analysis can be applied to determine the proper amount of erection materials and size of the stock yard needed.

**Table 7.** Sensitivity analysis setup and results.

		The Number of Erecting Materials						
	Productivity ( $\backslash$ )	12	14	16	18	20	22	24
The capacity of stockyard	17	0.258	0.237	0.235	0.250	0.276	0.307	0.339
	34	0.258	0.237	0.231	0.233	0.235	0.239	0.238
	51	0.259	0.232	0.235	0.237	0.235	0.239	0.236
	68	0.257	0.232	0.235	0.237	0.235	0.237	0.236
	85	0.258	0.236	0.235	0.234	0.235	0.239	0.235
	102	0.258	0.236	0.238	0.003	0.235	0.237	0.235
	119	0.258	0.232	0.235	0.237	0.238	0.240	0.236

**Figure 23.** Visual results of sensitivity analysis.

## 7. Conclusions

By executing the BIM-integrated simulation, we were able to obtain a dynamic productivity plan and calculate the project's per-hour rate of production. Compared to the traditional construction planning method, this system established a reliable construction plan from a bottom-up approach, meaning that we considered operational work and the relationships among the various activities, activities and resources, and resources themselves. This activity-based construction planning method improves reliability because the results are much closer to the actual schedule and the construction plan can be adjusted whenever the BIM model is modified. Also, when delays occur or resources change, using this BIM-integrated simulation framework is more flexible because the work is broken down into more detailed activities.

This research presented the development and application of the BIM-integrated simulation framework for reliable construction planning. From this framework, the operational level productivity is measurable, which means it can be used for whole-project planning. While BIM has been used in various construction fields ranging from predicting the energy performance of buildings to analyzing structural safety, BIM usage is relatively limited in the construction management field. This research presented a method capable of expanding BIM's utilization in the construction management domain. Also, since BIM information can now be reused by construction engineers establishing construction plans, the framework saves time, money, and effort that would otherwise be spent reproducing construction project data.

Furthermore, the developed framework presents a new perspective on construction planning by considering construction projects' uniqueness and complexity. Whenever the BIM model is modified during the work's progress, users can easily regenerate construction plans because BIM is integrated with the construction work simulation. Moreover, in the simulation environment, users can synthetically manipulate complex factors and resources. Since the current planning method uses historical data and heuristic adjustments, such plans depend on historical sample data and managers' knowledge and skill. That is, these construction plans cannot ensure consistency or accuracy. However, our framework facilitates more reliable planning by using the quantitative BIM-integrated simulation method. The end result is more reliable construction plans.

While the BIM-integrated simulation method created for this research is a technical breakthrough that represents a vast improvement in management efficiency, there were some limitations to this research. First, researchers should validate this framework by applying it to various test cases. Second, the framework should be employed in diverse types of construction beyond that of the steel erection work exemplified here. Finally, the simulation results should be made visual via a BIM model; doing so would extend the applicability of this framework.

**Acknowledgments:** This research was supported by the Basic Science Research Program through the National Research Foundation of Korea (NRF) funded by the Ministry of Science, ICT and Future Planning (No. NRF-2016R1A2B4015977).

**Author Contributions:** All authors read and approved this manuscript. All authors contributed to this research, discussed the results and implications, and were involved in the manuscript's development during all stages. WoonSeong Jeong led the implementation process of the integration framework. Soowon Chang implemented the case study and its experiments. JeongWook Son provided the main idea for this research and developed the integration framework as a principal investigator. June-Seong Yi discussed the main idea of this research.

**Conflicts of Interest:** The authors declare no conflict of interest

## References

1. AbouRizk, S.; Mohamed, Y. Optimal construction project planning. In Proceedings of the Winter Simulation Conference 2002, San Diego, CA, USA, 8–11 December 2002.
2. Mikulakova, E.; König, M.; Tauscher, E.; Beucke, K. Knowledge-based schedule generation and evaluation. *Adv. Eng. Inf.* **2010**, *24*, 389–403. [CrossRef]
3. Cooke, B.; Williams, P. *Construction Planning, Programming and Control*; John Wiley & Sons: New York, NY, USA, 2013.
4. Lee, S.H.; Pena-Mora, F.; Park, M. Dynamic planning and control methodology for strategic and operational construction project management. *Autom. Construct.* **2006**, *15*, 84–97. [CrossRef]
5. Alvanchi, A.; Lee, S.; AbouRizk, S. Dynamics of working hours in construction. *J. Construct. Eng. Manag.* **2011**, *138*, 66–77. [CrossRef]
6. Mao, X.; Zhang, X. Construction process reengineering by integrating lean principles and computer simulation techniques. *J. Construct. Eng. Manag.* **2008**, *134*, 371–381. [CrossRef]
7. Tucker, R.L. Management of construction productivity. *J. Manag. Eng.* **1986**, *2*, 148–156. [CrossRef]
8. Hao, Q.; Shen, W.; Xue, Y.; Wang, S. Task network-based project dynamic scheduling and schedule coordination. *Adv. Eng. Inf.* **2010**, *24*, 417–427. [CrossRef]
9. AbouRizk, S. Role of simulation in construction engineering and management. *J. Construct. Eng. Manag.* **2010**, *136*, 1140–1153. [CrossRef]
10. Eastman, C.; Teicholz, P.; Sacks, R. *BIM Handbook: A Guide to Building Information Modeling for Owners, Managers, Designers, Engineers and Contractors*; John Wiley & Sons: New York, NY, USA, 2011.
11. National Institute of Building Sciences. National Building Information Model Standard. Available online: <https://www.nationalbimstandard.org> (accessed on 11 October 2016).
12. Berner, F.; Kochkine, V.; Habenicht, I.; Spieckermann, S.; Vath, C. Simulation in manufacturing planning of buildings. In Proceedings of the 2013 Winter Simulation Conference on Simulation: Making Decisions in a Complex World; IEEE Press: Piscataway, NJ, USA, 2013; pp. 3306–3317.
13. Sargent, R.G. Verification and Validation of Simulation Models. Available online: <http://www.informs-sim.org/wsc11papers/016.pdf> (accessed on 11 October 2016).

14. Rabe, M.; Spieckermann, S.; Wenzel, S. A new procedure model for verification and validation in production and logistics simulation. In Proceedings of the 40th Conference on Winter Simulation; IEEE Press: Piscataway, NJ, USA, 2008; pp. 1717–1726.
15. König, M.; Beißert, U.; Steinhauer, D.; Bargstädt, H.-J. Constraint-based Simulation of Outfitting Processes in Shipbuilding and Civil Engineering. Available online: [http://www.simofit.com/Paper\\_EUROSIM\\_2007\\_koenig\\_beissert\\_steinhauer\\_bargstaedt.pdf](http://www.simofit.com/Paper_EUROSIM_2007_koenig_beissert_steinhauer_bargstaedt.pdf) (accessed on 11 October 2016).
16. Fu, J. A Microscopic Simulation Model for Earthmoving Operations. Available online: [http://transp-or.epfl.ch/heart/2012/latsis2012\\_submission\\_27.pdf](http://transp-or.epfl.ch/heart/2012/latsis2012_submission_27.pdf) (accessed on 11 October 2016).
17. Hajjar, D.; AbouRizk, S.M. Unified modeling methodology for construction simulation. *J. Construct. Eng. Manag.* **2002**, *128*, 174–185. [[CrossRef](#)]
18. Wu, I.-C.; Borrmann, A.; Beißert, U.; König, M.; Rank, E. Bridge construction schedule generation with pattern-based construction methods and constraint-based simulation. *Adv. Eng. Inf.* **2010**, *24*, 379–388. [[CrossRef](#)]
19. Wang, W.-C.; Weng, S.-W.; Wang, S.-H.; Chen, C.-Y. Integrating building information models with construction process simulations for project scheduling support. *Autom. Construct.* **2014**, *37*, 68–80. [[CrossRef](#)]
20. Halpin, D.W. CYCLONE-method for modeling job site processes. *J. Construct. Div.* **1977**, *103*, 489–499.
21. Zayed, T.M.; Halpin, D.W. Construction engineering I: Simulation as a tool for resource management. In Proceedings of the 32nd Conference on Winter Simulation; Society for Computer Simulation International: San Diego, CA, USA, 2000; pp. 1897–1906.
22. AbouRizk, S.M.; Hajjar, D. A framework for applying simulation in construction. *Can. J. Civ. Eng.* **1998**, *25*, 604–617. [[CrossRef](#)]
23. Xu, J.; AbouRizk, S. Product-based model representation for integrating 3D CAD with computer simulation. In Proceedings of the IEEE 1999 Winter on Simulation Conference Proceedings, Phoenix, AZ, USA, 5–8 December 1999; IEEE Press: Piscataway, NJ, USA; pp. 971–977.
24. Kamat, V.R.; Martinez, J.C. Validating complex construction simulation models using 3D visualization. *Syst. Anal. Model. Simul.* **2003**, *43*, 455–467. [[CrossRef](#)]
25. König, M.; Koch, C.; Habenicht, I.; Spieckermann, S. Intelligent BIM-based construction scheduling using discrete event simulation. In Proceedings of the IEEE 2012 Winter Simulation Conference (WSC), Berlin, Germany, 9–12 December 2012; IEEE Press: Piscataway, NJ, USA; pp. 1–12.
26. Howell, G.A. What is lean construction 1999. In Proceedings of the IGLC-7, Berkeley, CA, USA, 26–28 July 1999; pp. 1–10.
27. Koskela, L.; Howell, G.; Ballard, G.; Tommelein, I. The foundations of lean construction. In *Design and Construction: Building in Value*; Butterworth-Heinemann: Oxford, UK, 2002; pp. 211–226.
28. Sacks, R.; Radosavljevic, M.; Barak, R. Requirements for building information modeling based lean production management systems for construction. *Autom. Construct.* **2010**, *19*, 641–655. [[CrossRef](#)]
29. Melles, B. *What do We Mean by Lean Production in Construction?* Taylor & Francis: Oxfordshire, UK, 1997.
30. Shingo, S. *Non-Stock Production: The Shingo System of Continuous Improvement*; CRC Press: Boca Raton, FL, USA, 1988.
31. Tommelein, I.D.; Riley, D.R.; Howell, G.A. Parade game: Impact of work flow variability on trade performance. *J. Construct. Eng. Manag.* **1999**, *125*, 304–310. [[CrossRef](#)]
32. Tommelein, I.D.; Weissenberger, M. More just-in-time: Location of buffers in structural steel supply and construction processes. In Proceedings of the IGLC-7, Berkeley, CA, USA, 26–28 July 1999; pp. 109–120.
33. Radosavljević, M.; Horner, R.M.W. The evidence of complex variability in construction labour productivity. *Construct. Manag. Econ.* **2002**, *20*, 3–12. [[CrossRef](#)]
34. Yan, W.; Clayton, M.; Haberl, J.; Jeong, W.; Kim, J.; Kota, S.; Bermudez Alcocer, J.; Dixit, M. Interfacing BIM with Building Thermal and Daylighting Modeling. Available online: [http://www.ibpsa.org/proceedings/BS2013/p\\_1374.pdf](http://www.ibpsa.org/proceedings/BS2013/p_1374.pdf) (accessed on 11 October 2016).
35. Lee, G.; Sacks, R.; Eastman, C. Specifying parametric building object behavior (BOB) for a building information modeling system. *Autom. Construct.* **2006**, *15*, 758–776. [[CrossRef](#)]
36. Ku, K.; Taiebat, M. BIM experiences and expectations: The constructors' perspective. *Int. J. Construct. Educ. Res.* **2011**, *7*, 175–197. [[CrossRef](#)]



37. Barazzetti, L.; Banfi, F.; Brumana, R.; Gusmeroli, G.; Previtali, M.; Schiantarelli, G. Cloud-to-BIM-to-FEM: Structural simulation with accurate historic BIM from laser scans. *Simul. Model. Pract. Theory* **2015**, *57*, 71–87. [[CrossRef](#)]
38. Azhar, S.; Brown, J. BIM for sustainability analyses. *Int. J. Construct. Educ. Res.* **2009**, *5*, 276–292. [[CrossRef](#)]
39. Hu, Z.; Zhang, J. BIM-and 4D-based integrated solution of analysis and management for conflicts and structural safety problems during construction: 2. Development and site trials. *Autom. Construct.* **2011**, *20*, 167–180. [[CrossRef](#)]
40. Forbes, L.H.; Ahmed, S.M. *Modern Construction: Lean Project Delivery and Integrated Practices*; CRC Press: Boca Raton, FL, USA, 2010.
41. AbouRizk, S.M.; Halpin, D.W.; Wilson, J.R. Fitting beta distributions based on sample data. *J. Construct. Eng. Manag.* **1994**, *120*, 288–305. [[CrossRef](#)]
42. Moder, J.J.; Phillips, C.R.; Davis, E.W. *Project Management with CPM, PERT and Precedence Diagramming*; Van Nostrand Reinhold Company: New York, NY, USA, 1983.
43. Hong, T.; Hastak, M. Simulation study on construction process of FRP bridge deck panels. *Autom. Construct.* **2007**, *16*, 620–631. [[CrossRef](#)]



© 2016 by the authors; licensee MDPI, Basel, Switzerland. This article is an open access article distributed under the terms and conditions of the Creative Commons Attribution (CC-BY) license (<http://creativecommons.org/licenses/by/4.0/>).